

THE LAWRENCE SCHOOL SANAWAR

BILL OF QUANTITIES FOR THE CEMENT CONCRETE ROAD WORK, FIXING OF INTERLOCKING PAVERS ON ROAD, FIXING OF CHEQUERED TILES & ROAD MARKING WORKS

Please submit your rates for under mentioned items by 13-07-2017 in a sealed envelope

S.NO	DESCRIPTION OF WORK	UNIT OF MEASUREMENT	AREA (APPROX.)	RATE	AMOUNT
1	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of approved size, design & shape, laid in required colour and pattern over and including 20 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	SQ-M	120.00		
2	Providing and laying 80 mm thick factory made cement concrete interlocking paver block of approved size, design & shape, laid in required colour and pattern over and including 20 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	SQ-M	1000.00		
3	Providing ,laying and finishing of CHEQUERED TILES including filling of joints with the grey or white cement mixed with the pigment of the colour of the tile over the bedding of cement sand mortar with average thickness of 20 mm.	SQ-M	120.00		
4	Providing and laying CEMENT CONCRETE pavement of mix M-25 with the average thickness of 125 mm. The cement concrete mix shall be laid and finished with screed board vibrator , vacuum dewatering process and finally finished by floating, brooming with wire brush etc. complete as per specifications and directions of Engineer-in-charge. All side forms shall be of mild steel. The steel forms shall be of M.S. Channel sections and their depth shall be equal to the thickness of the pavement. Curing of the same needs to be done till the 7 days after the completion of the patch. Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material within all lifts and lead upto 1 km (by mechanical means).	SQ-M	1000.00		
5	Providing and applying 2.5 mm thick road marking strips (retro-reflective) of specified shade / colour using hot thermoplastic material by fully / semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour ,T&P, cleaning the road surface.	SQ-M	125.00		
	TOTAL				

Name of Contractor _____

Address _____

Contact No _____